



This device allows to select the kind of fuel manually or automatically. It also includes a "SAFETY CAR" function enabling the gas electrovalve only if the engine is running, in this way if it stops accidentally, the gas delivery stops immediately.



- 1. Fuel selecting key.
- 2. Gasoline running Indicator.
- 3. Gas running Indicator.
- 4. Indicators of fuel level and reserve.
- Choking timing (carburetor) or engine's rotation rate for the commutation (injection).
- RPM Connecting cable (coil's negative, tachometer or winding on coil's outlet).
- 7. Grounding
- 8. Positive after the keyswitch (10) with protection fuse (9).

- 9. Protection fuse.
- 10. Keyswitch.
- 11. Connection to the gasoline electrovalve, only carbureted vehicles.
- 12. "BLUE" cable + 12V when the vehicle runs with CNG.
- Connection for CNG fittings (Timing processor, emulators, etc.).
- 14. Electrovalve on pressure reducer.
- 15. Gas electrovalve.



#### Installation Check

#### Initial Pneumatic Test (Previous to CNG filling)

- · Pressure: 200bar
- Time: 10 minutes.
- · Element to be tested: high pressure piping and threaded connections
- · Fluid used: Inert gas (nitrogen)


#### TEST AND METHOD:

- · Close the service valves installed in the cylinders.
- · Open the filling valve.
- Connect the filling valve test line, using an adapter in the connection hole.
- The whole circuit must be subjected to testing time and pressure, checking the imperviousness in all the connection points with neutral soap foam.
- Once the test is finished, vent the system and open the cylinder valves.

#### Pneumatic Test (First CNG Filling)

- · Approximate pressure: 200 bar.
- Check with soapy water the connections of all those parts that accumulate gas, from the cylinder neck to the controller outlet.
- Once the checking is finished, clean with water and connect again the venting system.

#### Pneumatic Diagram



#### Cylinder installation for CNG Storage

The CNG containers must be placed following the line or profile of the vehicle and taking care that such line or profile protect the containers, even in case of overtum. The cylinders must be mounted with different types of bearings according to the model and type of vehicle to be converted. The place chosen for the fixing of the mounting screws must guarantee the necessary rigidity to achieve a firm attachment of the containers to the chassis.

#### a) CYLINDER VALVE INSTALLATION

- Fix the cylinder on an appropriate bearing for cylinder valve mounting and adjustment.
- . Check that the screw thread is clean and without strains.
- Wrap the screw thread 6 times with teflon tape clockwise, apply a thin layer of high-torque thread sealant (Loctite 680).
- Thread the valve to the cylinder and adjust with torquemeter with a 19kg-m to 21kg-m torque with a special wrench for the type of valve used.

#### b) INSTALLATION UNDER THE VEHICLE FLOOR:

Keep a 250mm minimum distance between the floor and the vehicle with maximum load. The installation must be performed using all the material provided in the kit, e.g. bearings, belts, bolts, covers, protectors, etc. according to the vehicle type or model.


#### c) CYLINDERS LOCATED IN THE CLOSED COMPARTMENT:



Venting tubes leading to the outside must be installed in the car vehicle or trunk to lead possible leaks in the cylinder valve. Use a venting bag (1) (in the case of using an electrical cylinder valve, the use of a venting bag is not necessary), venting tubes (2), venting pipes and accessories (3).



#### Location of Components Mechanical Installation




Tomasello Achille



1212N12013-30 Actual value 255-269

Remark: Required values were according to specification of design drawing, No activities were performed after the SGS inspector indicated QC manager the problem. The original hardness test record and drawing provided by manufactory as below:



Inspection Order No.: IN-TJ-5805-13023

[V: 02 June. 1st, 2012]

Page No.: 5 of 13

### NIPCO PLC

Issued from: Ibafo CNG Station

### **TECHNICAL CLEARANCE REPORT**

Customer no.:GGL/WS/2016/		=0=2		Date	e:		/2016
Certified that the vehicle bear	ing reg	istration	no				owned
by Mr/Mrs/M/s				4			
residing at							
(Phone nos							
technically fit for CNG cor	nversio	n. The	custome	er has	agre	ed t	o pay
N(					N	aira	only)
as down payment towards ins	tallatio	n of the	CNG cor	nversion	kit a	nd ha	as also
agreed to sign the CNG kit sa	ale agre	ement l	pefore co	nversio	n. Ple	ease	accep
the payment and advise us fo	r procee	eding wi	th the kit	fitment.			
Details of the vehicle to be	convert	ed:					
Make: M	lodel:			Type:(	)Ta	xi; (	)Pvt
Category: ( )Car; ( )Mini B	us; ( )	Pick-up		VIN:			
Engine No.:	(	Chassis	No.:				
Bank account details of cus			olds ATN	/l card: (	)YI	ES; (	)NO
Recommendations: Kit type: ( ) Open loop; (	) Clos	ed loop;	( ) Se	equentia	l type	e (4/6	/8 cyl)
Make of Kit: ( ) TA; ( ) SA	LUSTF	RI; ( ) \	/ANAZ				
Cylinder water capacity: 65 I	trs (indi	cate 30	50/60/65	/75/80)			
No. of cylinders: no.							
Make of Cylinder: ( ) EKC	;L; (	) CMBI	HCL; (	) KIOS	SHI		
Prepared & recommended by (Workshop Supervisor)	•			Authori (Works			ger)
Distribution: 1.Original copy: NOTE: PLEASE ATTACH COPY O	Mr.Pete F OWNE	r, F&A ( ERSHIP D	Copy: Wo	orkshop T (VEH. L	custo ICEN:	omer SE)	file
PROMOTE CNG- AN ECO			N & SAFE	VEHICU	LAR F	UEL	

	NIPCO	PLC,	NIPCO PLC, IBAFO CNG STATION	NO NO	*	Forn	Format No.:	CNG/WS/001
	PRE-CO!	VVERS	PRE-CONVERSION INSPECTION REPORT	IRT		Rev.	Rev. No: 0 Date	01/01/2015
Oate of Inspection			Whether converted before	erted before		<u> </u>	REMARKS IF ANY:	
Kit Fitment Workshop			(Yes/No).If Yes, do not convert	s, do not				
Vehicle Make			Model:					
Vehicle Registration No.			Type (Pvt/Taxi)	(1)				
Owner's Name			Phone No.:					
A. VEHICLE CONDITION/	129	B.	ENGINE CONDITION	Sta	Status	E. EN	ENGINE VARIABLES	
1 Exterior (Rody)	NOT OK	1 Fng	Fnaine Mounting	5	NOI OK	No No	No. of Cylinders	
			Overall Condition				Engine CC	
		3 Inle	Inlet Manifold			3 Fue	Fuel Injection System (Carburetor/ MPFI)	
Engine Bay/ compartment space for 4 mounting Regulator and other Kit		4 Exh	Exhaust Manifold			4 Dis	Ignition system-Full Distributor/Half Distributor/Coil (If Coil, indicate Nos.)	
5 Chassis		5 Eng	Engine Vibration			5 Thr	Throttle System (Electronic/Manual)	
		6 Idlir	Idling Speed (RPM)			6 TP	TPS Sensor (Yes/No)	
7 Exhaust Pipe/ Silencer		7 High	High Speed (RPM)			7 Ser	Sensor (MAP/MAF)	
C ELECTRICAL SYSTEMS		8 Eng	Engine Sound			8 0 8	Oxygen Sensor (Yes/No)	
1 Battery Condition		9 Air	Air Cleaner and its mounting bolt			9 CK	CKP sensor(Yes/No)	
2 Battery Voltage (to be measured)	>	10 Fue	Fuel Injectors			10 Air	Air Pump/valve (Yes/No)	
3 Battery Terminals & Wires		11 Car	Carburetor					
4 Spark plug Condition(remove all plugs & check)		12 Car Coll	Carburetor Dimensions (Outer Dia X Collar height in mm)	×				
5 HT Lead Condition		D. DO	<b>DOCUMENTATION VALIDITY</b>					
6 Ignition Coil Condition		1 Veh	Vehicle License(Valid/Not valid)			G. CC	COMPATIBILITY	
7 Overall wiring Condition		2 Veh	Vehicle License carries Owner's name (Yes/No)	ne		1 Int	Intake Manifold- (Steel/Aluminium/Plastic)	
8 Ignition Switch Condition		3 Insu	Insurance (Valid/Not Valid)			2 Mi	Mixer Availability (Yes/No)	
OBSERVATIONS:								
Vehicle is fit for conversion (Yes/No)		Type of k	Type of kit Recommended (Open Loop/Closed Loop/Sequential 4cvl/6cyl/8cyl)	Closed Loop/Sea	uential 4cv	1/6cvl/8	ScvI)	
Repairs to be done by Vehicle owner before submitting the vehicle for conversion(use separate sheet if the list is long)	ore submitting th	e vehicle	for conversion(use separate sh	eet if the list is lo	ong):			
1		3				5		
2		4				9		
Inspected by (Workshop Supervisor):	Verified	by (Work	Verified by (Workshop Manager):	Accepte	Accepted by (Vehicle Owner):	le Owr	ner):	
Name:	Name:			Name:				
Sign:	Sign			Sign				
Date:	Date:			Date:				

This checklist shall be carried out by the installer before

handing over	the vehic	cle to the cus	tomer	Format No.:		CNG/WS/003	
Δ	Details o	of Converted	Vehicle	Rev. No.: 0	Date	01/01/2015	
	77.515		70100-05-7 10 00-10	Green Gas Lim	nited, Iba	afo CNG Station,	
	a) Name and Address of Kit Installer				Ibafo, Ogun State		
	b) Make						
	c) Mode						
1		of Manufactu					
		ration Numb					
		e Identification	on Number				
		e Number					
		is Number f Conversion				***************************************	
		e on Date of					
1			er/ Contact Number				
1		f Operation	ny contact number	D: f . I			
		10		Bi-fuel			
В	Details o	of CNG Syste					
	1	CNG Cyline	Validity of hydro test certificate				
	1	1.2	Check for any corrosion on cylinder				
		1.3	Check mounting points free from corrosion and fractures		im nimitati		
	1						
		1.4	Ensure cylinder is securely mounted within the vehicle and			- 1	
	-	1.5	check tightness of nuts and bolts  Ensure round washer/ square plate of thickness not less than				
		1.5	2.5mm and of area not less than 3600 sqmm is used for	1			
	3		reinforcing the vehicle steel sheet metal where the cylinder /				
			cylinder bracket is anchored				
		1.6	Ensure anchorage bolt or studs shall be not less than 10mm				
			diameter and shall have strength grade class 8.8 as per ISO	1			
			4014				
		1.7	Ensure clamping bands are of minimum 30mm wide and	1			
			thickness of 3mm minimum (applicable for cylinder up to 100				
			Itrs. water capacity)				
		1.8	Ensure non-moisture retaining hard rubber or equivalent	1			
			material is provided on the inner side of the clamping bands	1			
			to prevent possibility of external corrosion of cylinder				
		1.9	Ensure minimum 5mm clearance is kept between cylinder		***************************************	<del></del>	
		1.3	and vehicle body structure				
		1.10	Ensure distance between cylinder valve and vehicle body			E CHELDING NE	
	2111-	778(763)	extremities shall not be less than 200mm				
	2	Cylinder Val					
		2.1	Check for any physical damage to valve				
		2.2	Check for correct operation of valve				
		2.3	Ensure burst disc is fitted				
		2.4	Check leakage using non corrosive foaming agent or				
			methane leak detector				
	3						
		3.1	Ensure installation of ventilation bag is gas tight				
		3.2	Ensure ease of operation of cylinder valve				
	4	Refilling V			-		
		4.1	Ensure refilling valve is securely mounted  Check for dust protection cap				
		4.2	Check leakage using non corrosive foaming agent or	32.4			
		4.5	methane leak detector				
The second second second second		And the second second second					

5	Fuel line		
	5.1	Check for any damage and corrosion on CNG fuel line	
ı	5.2	Ensure fuel line is securely mounted	
	5.3	Ensure fuel line is clamped by clips spaced not more than	
		600mm apart	
	5.4	Ensure distance between fuel line and exhaust heat source	
	T.8/3	shall not be less than 75mm	
	5.5	Check for deformation of 'U' and Pigtail bends provided in	
- 1		high pressure piping for flexibility	
	5.6	Ensure fuel line is protected and shielded where necessary	
-	5.7	Check leakage using non corrosive foaming agent or	
		methane leak detector	
6	Shut off v	alve (Solenoid Valve) wherever separately provided	
T	6.1	Ensure shut off valve is securely mounted	
	6.2	Check operation for "Close & Open" as required	
r	6.3	Check leakage using non corrosive foaming agent or	
		methane leak detector	
7	Pressure (	Gauge with Sensor	
	7.1	Ensure CNG pressure gauge is securely mounted	
-	7.2	Check leakage using non-corrosive foaming agent or	
	7.2	methane leak detector	
8	Datual Cal		
$\overline{}$	8.1	enoid Valve with By-pass Device  Ensure petrol solenoid valve is securely mounted	
-		Check for correct operation	
-	8.2 8.3	Check petrol hose for any cracks	
H	8.4	Ensure sufficient flexibility for engine movement	
-	8.5	Ensure hose joints are leak free	
9	Gas-Air M		
7	9.1	Ensure gas-air mixer is securely mounted	
-	9.2	Ensure back-fire deflector where applicable	
10	Regulator		
1	10.1	Ensure regulator is securely mounted	
-	10.2	Ensure mounting is as close to the engine carburetor position	
1	10.2	as convenient	
1	10.3	Ensure minimum distance of 150mm from exhaust system.	
	10.5	Where this distance is less than 150mm, ensure shield is	
		provided for protection from radiant heat and any	
- 1		impingement from exhaust gases due to exhaust system	
- 1		failure	
+	10.4	Ensure no gas by-pass after engine has stopped	
H	10.5	Check leakage using non-corrosive foaming agent or	
	10,5	methane leak detector	
11	Fuel Selec	ctor Switch	
T	11.1	Ensure fuel selection switch is securely mounted on the	
		dashboard	
+	11.2	Ensure the location is convenient for the driver to operate	
	11.2	with ease	
1	11.3	Ensure connections are properly done as per recommended	
	11.3	connection diagram	
- 1	11.4	Ensure fuel gauge (LED lights) is calibrated for various levels /	

12		Control Unit (for Fuel Injection Vehicles)	
	12.1	Ensure the Electronic Control module is securely mounted	
	12.2	Ensure the mounting is in vertical position with cable facing down to avoid entry of water	
	12.3	Ensure the cables and module is away from heat source	
	12.0	(radiation, exhaust manifold e.t.c) and high voltage cables,	
		ignition coil, spark plugs, distributor e.t.c.	
H	12.4	Ensure connections are properly done as per recommended	The state of the s
	12.7	connection diagram	
	12.5	Ensure the pin connectors of wiring harnesses (signal harness	
- 1		& Injector harness) are connected to respective	
		devices/sensors as per recommended connection diagram.	
ŀ	12.6	Ensure the gas injectors are located away from heat source	
-	12.7	Ensure correct gas flow direction of filter	and the second s
-	12.8	Ensure the length of hoses between gas injectors and the	
		manifold is not more than 250mm	TO STATE OF THE PROPERTY OF TH
13	Timing Ac	dvance Processor	
T	13.1	Ensure Timing Advance Processor (TAP) is securely mounted	
1	13.2	Ensure the mounting is in vertical position with cables facing	
		down to avoid entry of water	
	13.3	Ensure TAP is away from heat source (radiation, exhaust manifold e.t.c)	
ŀ	13.4	Ensure cables and module of TAP is away from high voltage	
		cables, ignition coil, spark plugs, distributor e.t.c.	
-	13.5	Ensure connections (positive & negative) are properly done	
	13.3	as per recommended connection diagram	
	VI D Conti	rol unit(for vehicles fitted with closed loop system )	
14		Ensure XLP control unit is securely mounted	
-	14.1	Ensure the mounting is in vertical position with cables facing	
- 1	14.2	down to avoid entry of water	
+	14.3	Ensure XLP control unit is away from heat sources (radiation,	
1	14.5	exhaust manifold e.t.c.) and high voltage cables, ignition	
		coils, spark plugs, distributor e.t.c.	
-	14.4	Ensure connections are properly done as per recommended	
	14.4	connection diagram	
ı	14.5	Ensure the pin connectors of wiring harness are connected to	
- 1		respective devices/ sensors as per recommended connection	
		diagram	
15	Electrical	Wiring	
	15.1	Ensure current limiting device (fuse) is fitted	
	15.2	Ensure all electrical connections are secure	
	15.3	Ensure terminals are insulated to prevent shorting	
	15.4	Ensure wiring is properly installed, taped, clipped and	
		contained in a loom along its length	
		ace Plate	
16	Compliar	ice riace	
16	Compliar 16.1	Ensure compliance plate is securely installed near the refilling	
16		Ensure compliance plate is securely installed near the refilling valve and carries correct markings of the following	
16	16.1	Ensure compliance plate is securely installed near the refilling valve and carries correct markings of the following parameters:	
16	16.1	Ensure compliance plate is securely installed near the refilling valve and carries correct markings of the following parameters:  Date of conversion	
16	16.1 16.2 16.3	Ensure compliance plate is securely installed near the refilling valve and carries correct markings of the following parameters:  Date of conversion  Name of CNG workshop	
16	16.1 16.2 16.3 16.4	Ensure compliance plate is securely installed near the refilling valve and carries correct markings of the following parameters:  Date of conversion  Name of CNG workshop  Vehicle number	
16	16.1 16.2 16.3 16.4 16.5	Ensure compliance plate is securely installed near the refilling valve and carries correct markings of the following parameters:  Date of conversion  Name of CNG workshop  Vehicle number  Kit serial number and make	
16	16.1 16.2 16.3 16.4 16.5 16.6	Ensure compliance plate is securely installed near the refilling valve and carries correct markings of the following parameters:  Date of conversion  Name of CNG workshop  Vehicle number  Kit serial number and make  Cylinder serial number and make	
16	16.1 16.2 16.3 16.4 16.5 16.6	Ensure compliance plate is securely installed near the refilling valve and carries correct markings of the following parameters:  Date of conversion  Name of CNG workshop  Vehicle number  Kit serial number and make  Cylinder serial number and make  Water capacity (Ltr)	
16	16.1 16.2 16.3 16.4 16.5 16.6	Ensure compliance plate is securely installed near the refilling valve and carries correct markings of the following parameters:  Date of conversion  Name of CNG workshop  Vehicle number  Kit serial number and make  Cylinder serial number and make	

	17	Identification	on Label in Front and Rear as per Approved Design	
			Ensure identification label is pasted on the front and rear of the vehicle for proper visibility from front & rear sides	
	18	Performan	ce Test	
		18.1	Ensure engine idle RPM is correct	
		18.2	Ensure vehicle pick-up is correct and not sluggish	
		18.3	Ensure engine power is good at high RPM	
		18.4	Ensure exhaust emission parameters are within acceptable limits in idling condition (CO, HC and NOx)	
	19	Documenta	ation	
			Ensure installation certificate is duly signed by vehicle owner and by witnessee	
			Ensure the following set of documents are given to vehicle owner after successful CNG conversion	
			- Installation certificate	
			- Cylinder hydrotest certificate	
			- CNG owner's manual	
			Ensure photocopy of the following vehicle / owner documents are kept in record:	
			- Vehicle Licence	
			- Insurance Certificate	
		We minded a second	- Vehicle Owner's driving licence	
			<ul> <li>Vehicle Owner's National I.D card (if available)</li> </ul>	
	20		Operation Assistance	
			Ensure vehicle owner/driver is well informed on safe operating procedures of vehicle in CNG/petrol mode; maintenance instructions; safety awareness and precautions to be taken while servicing/repairing the vehicle	
	-			

Checked by:	Verified by:
Name:	Name:
Date:	Date:
Sign:	Sign: