

# Shell Petroleum Development Company of Nigeria

Classification Status: Restricted

May 2021 DOCUMENT NUMBER

SPDC-2021-05-00000078

# Disabling of FYNAG Offshore Pressure Safeguarding Desktop Safety Review Report

Proprietary Information: This document contains proprietary information and may not be partly or wholly reproduced without prior written permission from Shell Petroleum Development Company						
Revision	Date	Description	Originator	Checker	Approver	
A01	25-05-2021	Issued for Approval	Izu Iloma	Linda Ajilore	Tawheed Olayiwola	

### **REVISION PHILOSOPHY**

All revisions for review will be issued at RO1, with subsequent RO2, RO3, etc. as required.

All revisions approved for issue or design will be issued at A01, with subsequent A02, A03, etc. as required.

Documents approved for Construction will be issued at CO1, CO2, and CO3 respectively.

Documents or drawings revised as "As built" will be issued as Z01, Z02 Z03 etc.

Narrative sections revised from previous approved issues are to be noted in the table below and/or highlighted in the RH margin (using the appropriate revision status) thus: A02

Previous revision highlighting to be removed at subsequent issues.

Drawings/diagrams revised from previous approved issues are highlighted by 'clouding' the affected areas and by the use of a triangle containing the revision status.

#### **REVISION HISTORY**

Rev. No.	Date of Issue	Reason for change			
RO1	05-05-2021	Issued for Review and Comments			

#### **EXECUTIVE SUMMARY**

This report outlines the methodology and results of the Desktop Safety Review study for the disabling of the offshore pressure safeguarding for the FYNAG well (FORC 153) flowline. The study was held on the 30<sup>th</sup> of April 2021 via Skype virtual meeting.

The objective of the DSR is to identify potential process & operational hazards, failures and operability problems associated with this temporary change on the entire flowline system.

The scope was treated in 1 study node. The DSR participants comprised of representatives from the Asset and various relevant disciplines present at the meetings.

No recommendations were made for resolution and tracked to closure in the subsequent phases of the project.

This report is arranged in a general part relevant to introduction, process description, team members, methodology and findings followed by 3 appendices:

Appendix A: DSR Study Worksheets

Appendix B: Action Completion Sheet

Appendix C: DSR PEFS

## TABLE OF CONTENTS

EXEC	JTIVE SU	JMMARY	3			
ABBR	EVIATIC	NS	5			
1.0	INTRODUCTION					
	1.1	Project Background and Scope	6			
2.0	Study	7				
	2.1	Study Objectives	7			
	2.2	Timing and Team Composition	7			
	2.3	Recording and Reporting	7			
3.0	FINDII	DINGS and recommendations				
4.0	Conclu	sion9				
Appendix A.		DSR Worksheets	10			
Appendix B.		Action Completion Sheet	11			
Appendix C.		PEFS	12			

### **ABBREVIATIONS**

FYIP Forcados Yokri Integrated Project

MMscf Million Standard Cubic Feet

NAG Non-Associated Gas

PEFS Process Engineering Flow Scheme

PFD Process Flow Diagram

P&ID Process & Instrument Drawing

SOP Standard Operating Procedure

SPDC Shell Petroleum Development Corporation

#### 1.0 INTRODUCTION

### 1.1 Background and Scope

The FYIP NAG FORC 153 (FYNAG) is a Non-Associated Gas Well from Estuary JA Cluster, developed and currently producing to the North Bank CPF facility. The FYIP NAG Well has the potential to supply about 50MMscfd of Gas to the North Bank CPF for processing and onward transportation to the Escravos Lagos Pipeline system. The NAG well fluid is transported via a 6" X 5km DSS flowline fully rated (276barg) up to its inlet Pig receiver kicker line at Northbank CPF; downstream of this are class 900# piping and equipment to the Inlet production manifold of the NAG slug catcher.

The 6" X 5km flowline which was commissioned in November of 2020, though fully rated to the CITHP of the well (276Barg), also has pressure safeguarding instrumentation and Shutdown valves offshore (100-PZS-104A HH, 100-PZS-104B LL, 100-XZV-104) and onshore at the CPF (3123-PZA-001 HH and LL and 3123-UZV-001).

It was observed during commissioning and Startup of the NAG well that the design pressure (160barg) of the Offshore HH and LL pressure safeguarding instrumentation on the flowline is below the well CITHP (276barg). This implies there is a risk of instrumentation blow out or LOPC in the event that 100-XZV-104 closes. The likelihood of this risk is high because the pressure instrumentation is installed upstream of shutdown valve 100-XZV-104. See Figure 1.0 below.

The scope of this review is to assess the impact of removal of the offshore pressure safeguarding on the entire flowline system




Figure 1.0: FYNAG Flowline Offshore Pressure safeguarding set up

### 2.0 STUDY METHODOLOGY

### 2.1 Study Objectives

The objectives of this study are:

 To identify hazards and operability issues, if any, on the agreed scope and to make recommendations to address the identified issues.

Verify that the safeguards for all credible process deviations are adequate and make recommendations
where necessary.


## 2.2 Timing and Team Composition

The Study was held virtually on the 30<sup>th</sup> of April 2021 via Skype for Business. Participants comprised of a good mix of experienced personnel that are aware of the scope and associated issues.

The multi-discipline team was drawn from across various functions/disciplines and the asset team.

Table 1: Attendance List

Name	Position	Company
lloma Izu	Process/Technical Safety Specialist / Facilitator	SPDC
Linda Ajilore	Senior Process Engineer	SPDC
Egodo Edward	Field Supervisor (Ops), Forcados Area	SPDC
Dafiadje Oghenovo	Snr Project Engineer, FYIP Onshore	SPDC
Taylor, Paul	Commissioning Engineer – DOMGAS and FYIP	SPDC



# 2.3 Recording and Reporting

During the study, all foreseeable and credible hazards and process deviations identified by the team were recorded on a Worksheet. See Appendix A.

## 3.0 FINDINGS AND RECOMMENDATIONS

No recommendations were identified for resolution or further investigation. The detailed worksheet is provided in Appendix A.

## 4.0 CONCLUSION

The DSR was carried out by participants from various disciplines possessing the appropriate skills, experience, and knowledge required for an effective study. The output of this DSR is presented in Appendix A of this report.

# Appendix A. DSR Worksheets

Hazard: Hydrocarbon Gas. Rating: P-5C, A-5B, C-5B, E-2D

S/N	CAUSE	CONSEQUENCE(S)	EXISITNG SAFEGUARDS	RECOMMENDATION	ACTION PARTY
1	Closure of 100-BA-123 upstream	Blocked outlet for FYNAG well leading to pressure build-up to	Manual valves are Locked open (LO)	•	•
•	the Barred Tee	CITHP	<ul> <li>High pressure trip on 100-PZH-101 trips the well</li> </ul>		
		Loss of Production from NAG Well	Line is fully rated to CITHP of 276 barg		
2	• Closure of 100-BA-121/132	Blocked outlet for FYNAG well leading to pressure build-up to	Manual valves are Locked open (LO)	•	•
_	downstream the Barred Tee	CITHP	High pressure trip on 100-PZH-101 trips the well		
		Loss of Production from NAG Well	Line is fully rated to CITHP of 276 barg		
3	• Closure of BA-1101/1102	Blocked outlet for FYNAG well leading to pressure build-up to	Manual valves are Locked open (LO)	•	•
	upstream the pig receiver A-3123		High pressure trip on 100-PZH-101 trips the well		
		Loss of Production from NAG Well	Line is fully rated to CITHP of 276 barg		
4	• Fail closure of 3123-UZV-001	Blocked outlet for FYNAG well leading to pressure build-up to	High pressure trip on 100-PZH-101 trips the well	•	•
-	upstream the pig receiver A-3123	CITHP	<ul> <li>Line is fully rated to CITHP of 276 barg</li> </ul>		
		Loss of Production from NAG Well			
5	• Closure of BA-1111 downstream	Blocked outlet for FYNAG well leading to pressure build-up to	Manual valves are Locked open (LO)	•	•
	the pig receiver A-3123	CITHP	High pressure trip on 100-PZH-101 trips the well		
		Loss of Production from NAG Well	<ul> <li>Line is fully rated to CITHP of 276 barg</li> </ul>		
6	• Control loop failure of 3123-	Blocked outlet for FYNAG well leading to pressure build-up to	<ul> <li>High Pressure trip on 3123-PZA-001 trips 3123-UZV-001</li> </ul>	•	•
	FQIC-003 resulting in closed		<ul> <li>High pressure trip on 100-PZH-101 trips the well</li> </ul>		
	position of 3123-FCV-003	in potential for LOPC with fires, environmental impact, asset	<ul> <li>Flow Line is fully rated to CITHP of 276 barg</li> </ul>		
		damage and personnel injuries.			
		Loss of Production from NAG Well			
7	• Fail closure of 3123-UZV-003		<ul> <li>High Pressure trip on 3123-PZA-001 trip 3123-UZV-001</li> </ul>	•	•
·	upstream the slug catcher V-3123		<ul> <li>High pressure trip on 100-PZH-101 trips the well</li> </ul>		
		in potential for LOPC with fires, environmental impact, asset	<ul> <li>Flow Line is fully rated to CITHP of 276 barg</li> </ul>		
		damage and personnel injuries.			
		Loss of Production from NAG Well			
8	• Closure of BA-1143/1138/1140		<ul> <li>Manual valves are Locked open (LO)</li> </ul>		•
	/1130A upstream the slug		High Pressure trip on 3123-PZA-001 trips 3123-UZV-001		
	catcher V-3123	in potential for LOPC with fires, environmental impact, asset	High pressure trip on 100-PZH-101 trips the well		
		damage and personnel injuries.	<ul> <li>Flow Line is fully rated to CITHP of 276 barg</li> </ul>		
		Loss of Production from NAG Well			
9	CH-1102 failed internals	Blocked outlet for FYNAG well leading to pressure build-up to	High Pressure trip on 3123-PZA-001 trip 3123-UZV-001	•	•
		CITHP with over pressurization of the #900 rated piping resulting	High pressure trip on 100-PZH-101 trips the well		
		in potential for LOPC with fires, environmental impact, asset	<ul> <li>Flow Line is fully rated to CITHP of 276 barg</li> </ul>		
		damage and personnel injuries.			
		Loss of Production from NAG Well			
10	Any SB in wrong position after	Unable to start up.	Pre-start up and commission Checks	•	•
	maintenance	Blocked outlet for FYNAG well leading to pressure build-up to	High Pressure trip on 3123-PZA-001 trips 3123-UZV-001		
		CITHP with over pressurization of the #900 rated piping resulting	High pressure trip on 100-PZH-101 trips the well		
		in potential for LOPC with fires, environmental impact, asset	<ul> <li>Flow Line is fully rated to CITHP of 276 barg</li> </ul>		
		damage and personnel injuries.			
11	• Line rupture due to external	LOPC to environment leading to environmental impact	Low pressure trip on 100-PZL-101 trips the well	•	•
	impact or integrity related issues	Low flowline pressure leading to reduced production	<ul> <li>Low Pressure trip on 3123-PZA-001 trips 3123-UZV-001</li> </ul>		

# Appendix B. Action Completion Sheet

HAZOP Action Completion Sheet									
System				Node	de Date of HAZOP				
Guidewords	iation	Consequence							
No Flow					· •				
Protection/Evaluation	Ro in	ank Acti	on						
•									
ACTION PARTY RESPONSE	Action Owner Ac		Action No	ction No.		Action Due Date			
	Response:								
	Supporting Dro	awings/Document	tation Re	ference l	Nos.:				
	this section ar					this section and the	complete all boxes in then pass to Project		
	Responsible Party:		Signature:		Date:		HSE Engineer after Discipline Technical Authority approval.		
STATUS									
APPROVAL BY DISCIPLINE	Comments:								
TECHNICAL AUTHORITY						Status 2 when this	Status 2 when this section is		
AUTIONITI	Discipline Tech	nical Authority:	Signo	ıture:	Date:	completed.			
ACCEPTED BY PROJECT LEAD	Comments:		1		•				
TECH HSE ENGINEER						Status 3 when this	Status 3 when this section is		
	Project Lead Technical HSE Engineer		Signo	iture:	Date:	completed.	completed.		
PROJECT APPROVAL	Project Lead:		Signo	iture:	Date:	Action closed out.	Status 4.		
, 1110, 71						, and a doubte doi:			

#### Description:

1: Under consideration by Action Party

Status 3: Accepted by Safety Engineer pending close out

2: Approved by Discipline Technical Authority

Status 4: Closed Out

# Appendix C. PEFS

